

Detailed Estimate

OD/346/3309/116316/393724/00066699 : Const. of cc road from Jitendra Behera house to Pradip Behera house vill

Bharadapada of Jadida G.P

Block : Soro, Gram Panchayat : Jadia

Created By: Sanjib Kumar Mohapatra

1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	GW	2.000	34.000	0.250	0.200	0.000	3.400	-
Total Quantity					3.4 cum (cum)		3.4 Cum (Cubic Meter)	
Amount					3.4 X 240.77592		818.64	
2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	GW	2.000	35.000	0.200	0.050	0.000	0.700	-
ii	Road	1.000	35.000	2.000	0.100	0.000	7.000	-
Total Quantity					7.7 cum (cum)		7.7 Cum (Cubic Meter)	
Amount					7.7 X 1447.535232		11146.02	
3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	GW	2.000	34.000	0.200	0.300	0.000	4.080	-

ii	Road	1.000	34.000	1.800	0.100	0.000	6.120	-
Total Quantity					10.2 cum (cum)		10.2 Cum (Cubic Meter)	
Amount					10.2 X 5908.5517827		60267.23	
4. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc								
Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	GW	2.000	2.000	34.000	0.300	0.000	40.800	-
ii	Road	1.000	2.000	34.000	0.100	0.000	6.800	-
Total Quantity					47.6 Sqm (Sqm)		47.6 Sqm (Square Meter)	
Amount					47.6 X 216.23489289764		10292.78	
5. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum								
Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Road	1.000	34.000	2.200	0.100	0.000	7.480	-
Total Quantity					7.48 cum (cum)		7.48 Cum (Cubic Meter)	
Amount					7.48 X 7355.2513609		55017.28	
Total Amount							137541.95	
Addition								
Provision for Contingency (+) @							558.05	
Display Citizen Board (+) @							500.00	
Any Other Lumpsum (+) @							1400.00	

Provision for survey investigation and quality control (+) @	
Total Addition	2458.05
Grand Net Total Amount	140000.00

Sanjib Kumar Mohapatra
JE
Soro Block

Nirmala Kanta Parida
AEE
Soro Block

Satyanath Naik
BDO
Soro Block