

## Detailed Estimate

**OD/369/3537/275125/409868/00066230 : Maint of road with CC\Gr-II metalling from pachhipal to Harijan sahi**  
**Block : Brahmagiri, Gram Panchayat : Balikerapachhipala**  
**Created By:GITANJALI BEHERA**

<b>1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	earth work	1.000	40.000	3.000	0.250	1.000	30.000	-
Total Quantity					30 cum (cum)		30 Cum (Cubic Meter)	
Amount					30 X 240.77592		7223.28	
<b>2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b>								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	filling sand	1.000	40.000	3.000	0.100	1.000	12.000	-
Total Quantity					12 cum (cum)		12 Cum (Cubic Meter)	
Amount					12 X 1065.310832		12783.73	
<b>3. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b>								
Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	road	1.000	40.000	1.000	0.350	1.000	14.000	-
Total Quantity					14 Sqm (Sqm)		14 Sqm (Square Meter)	

<b>Amount</b>					<b>14 X 216.23489289764</b>	<b>3027.29</b>		
<b>4. Concrete (AR0303a) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal</b>								
Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	road	1.000	40.000	3.000	0.100	1.000	12.000	-
Total Quantity					12 cum (cum)		12 Cum (Cubic Meter)	
<b>Amount</b>					<b>12 X 6056.30102044</b>	<b>72675.61</b>		
<b>5. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum</b>								
Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	road	1.000	40.000	3.000	0.100	1.000	12.000	-
Total Quantity					12 cum (cum)		12 Cum (Cubic Meter)	
<b>Amount</b>					<b>12 X 7732.38267228</b>	<b>92788.59</b>		
<b>Total Amount</b>							<b>188498.50</b>	
<b>Addition</b>								
Provision for Contingency (+) @							8000.00	
Display Citizen Board (+) @							1000.00	
Any Other Lumpsum (+) @							501.00	
Provision for survey investigation and quality control (+) @							2000.00	
<b>Total Addition</b>							<b>11501.00</b>	
<b>Grand Net Total Amount</b>							<b>199999.50</b>	

**GITANJALI BEHERA**  
**JE**  
**Brahmagiri Block**

**Sudipta Rout**  
**AEE**  
**Brahmagiri Block**

**PuriBdoBrahmagiri**  
**BDO**  
**Brahmagiri Block**