

Detailed Estimate

OD/373/3574/121544/384126/00066575 : CONSTRUCTION OF CC ROAD AT BAGBUD PANCHAM SA HOUSE TO PUTUL DASH HOUSE

Block : Bargaon, Gram Panchayat : Jarngloi

Created By: LOCHAN PRADHAN JE

1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	Road	1.000	88.000	3.100	0.100	0.000	27.280	-
ii	Cut off	2.000	88.000	0.200	0.100	0.000	3.520	-
Total Quantity					30.8 cum (cum)		30.8 Cum (Cubic Meter)	
Amount					30.8 X 240.77592		7415.90	
2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	Road	1.000	88.000	2.700	0.050	0.000	11.880	-
ii	Cut off	2.000	88.000	0.200	0.050	0.000	1.760	-
Total Quantity					13.64 cum (cum)		13.64 Cum (Cubic Meter)	
Amount					13.64 X 790.631232		10784.21	
3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction

i	Road	1.000	88.000	3.100	0.100	0.000	27.280	-
ii	Cut off	2.000	88.000	0.200	0.100	0.000	3.520	-
Total Quantity					30.8 cum (cum)		30.8 Cum (Cubic Meter)	
Amount					30.8 X 5808.86880452		178913.16	
4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum								
Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Road	1.000	88.000	3.100	0.095	0.000	25.916	-
Total Quantity					25.916 cum (cum)		25.916 Cum (Cubic Meter)	
Amount					25.916 X 7266.16979924		188310.06	
5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc								
Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Road	2.000	88.000	0.200	0.000	0.000	35.200	-
Total Quantity					35.2 Sqm (Sqm)		35.2 Sqm (Square Meter)	
Amount					35.2 X 217.02363744964		7639.23	
Total Amount							393062.56	
Addition								
Provision for Contingency (+) @							3930.63	
Display Citizen Board (+) @							3000.00	

Any Other Lumpsum (+) @	6.80
Provision for survey investigation and quality control (+) @	
Total Addition	6937.43
Grand Net Total Amount	399999.98

LOCHAN PRADHAN JE
JE
Bargaon Block

SUNIL MURMU
AEE
Bargaon Block

BDO Bargaon
BDO
Bargaon Block