

Detailed Estimate

OD/365/3487/120038/390721/00074679 : CONST. OF CC ROAD FROM MENKA SAHU HOUSE CHHAKA TO UPEN SAHU HOUSE CHHAKA IN WORD NO-4 CHHELIA-B
Block : Badasahi, Gram Panchayat : Balabhadrapur
Created By: BASANTA MURMU

1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cutoff wall	2.000	97.500	0.180	0.180	0.000	6.318	-
ii	Cutoff Wall end	2.000	2.910	0.180	0.180	0.000	0.189	-
Total Quantity					6.506568 cum (cum)		6.506568 Cum (Cubic Meter)	
Amount					6.506568 X 240.77592		1566.62	
2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cutoff End	2.000	97.500	0.180	0.050	0.000	1.755	-
ii	cutoff end	2.000	2.910	0.180	0.500	0.000	0.524	-
iii	bed	1.000	97.500	2.910	0.100	0.000	28.373	-
Total Quantity					30.6513 cum (cum)		30.6513 Cum (Cubic Meter)	
Amount					30.6513 X 1457.625132		44678.11	
3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal								

Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cutoff wall	2.000	97.500	0.180	0.180	0.000	6.318	-
ii	cutoff end	2.000	2.910	0.180	0.180	0.000	0.189	-
iii	road	1.000	97.500	2.910	0.100	0.000	28.373	-
Total Quantity					34.879068 cum (cum)		34.879068 Cum (Cubic Meter)	
Amount					34.879068 X 6638.8398173		231556.55	

4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	road	1.000	97.500	3.350	0.070	0.000	22.864	-
Total Quantity					22.86375 cum (cum)		22.86375 Cum (Cubic Meter)	
Amount					22.86375 X 8144.2970141		186209.17	

5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	cutoff	4.000	97.500	0.000	0.180	0.000	70.200	-
ii	cutoff end	2.000	3.350	0.000	0.180	0.000	1.206	-
iii	PCC	2.000	97.500	0.000	0.100	0.000	19.500	-

iv	WC	2.000	97.500	0.000	0.070	0.000	13.650	-
Total Quantity					104.556 Sqm (Sqm)		104.556 Sqm (Square Meter)	
Amount					104.556 X 216.23489289764		22608.66	
Total Amount							486619.10	
Addition								
Provision for Contingency (+) @							5000.00	
Display Citizen Board (+) @							5000.00	
Any Other Lumpsum (+) @							3380.89	
Provision for survey investigation and quality control (+) @								
Total Addition							13380.89	
Grand Net Total Amount							499999.99	

BASANTA MURMU
JE
Badasahi Block

DASHARATH MOHANTA
AEE
Badasahi Block

BANAJA DAS
BDO
Badasahi Block