

## Detailed Estimate

**OD/356/3397/118329/401802/00100091 : Construction of Concrete road from udayanagar chhaka to hatimada**  
**Block : Dharmasala, Gram Panchayat : Areikana**  
**Created By:MANA DEOGAM**

| <b>1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>  |             |       |        |       |       |                              |                                   |           |
|--|-------------|-------|--------|-------|-------|------------------------------|-----------------------------------|-----------|
| Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge  |             |       |        |       |       |                              |                                   |           |
| SI No  | Description | No    | L      | B     | D     | CF                           | Quantity                          | Deduction |
| i  | wall        | 2.000 | 55.500 | 0.225 | 0.200 | 0.000                        | 4.995                             | -         |
| <b>Total Quantity</b>  |             |       |        |       |       | <b>4.995 cum (cum)</b>       | <b>4.995 Cum (Cubic Meter)</b>    |           |
| <b>Amount</b>  |             |       |        |       |       | <b>4.995 X 240.77592</b>     | <b>1202.68</b>                    |           |
| <b>2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b>  |             |       |        |       |       |                              |                                   |           |
| Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.   |             |       |        |       |       |                              |                                   |           |
| SI No  | Description | No    | L      | B     | D     | CF                           | Quantity                          | Deduction |
| i  | wall        | 2.000 | 55.500 | 0.225 | 0.050 | 0.000                        | 1.249                             | -         |
| ii   | road        | 1.000 | 55.500 | 3.050 | 0.100 | 0.000                        | 16.928                            | -         |
| <b>Total Quantity</b>  |             |       |        |       |       | <b>18.17625 cum (cum)</b>    | <b>18.17625 Cum (Cubic Meter)</b> |           |
| <b>Amount</b>  |             |       |        |       |       | <b>18.17625 X 918.951732</b> | <b>16703.10</b>                   |           |
| <b>3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b>   |             |       |        |       |       |                              |                                   |           |
| Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. |             |       |        |       |       |                              |                                   |           |
| SI No  | Description | No    | L      | B     | D     | CF                           | Quantity                          | Deduction |
| i  | wall        | 2.000 | 55.500 | 0.225 | 0.250 | 0.000                        | 6.244                             | -         |
| ii   | road        | 1.000 | 55.500 | 3.050 | 0.100 | 0.000                        | 16.928                            | -         |

|                |                             |                            |
|----------------|-----------------------------|----------------------------|
| Total Quantity | 23.17125 cum (cum)          | 23.17125 Cum (Cubic Meter) |
| Amount         | 23.17125 X<br>6016.59597316 | 139412.05                  |

**4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.

| Sl No          | Description | No    | L      | B     | D                          | CF    | Quantity                  | Deduction |
|----------------|-------------|-------|--------|-------|----------------------------|-------|---------------------------|-----------|
| i              | road        | 1.000 | 55.500 | 3.050 | 0.100                      | 0.000 | 16.928                    | -         |
| Total Quantity |             |       |        |       | 16.9275 cum (cum)          |       | 16.9275 Cum (Cubic Meter) |           |
| Amount         |             |       |        |       | 16.9275 X<br>7525.06336992 |       | 127380.51                 |           |

**5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc**

Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

| Sl No          | Description | No    | L      | B     | D                             | CF    | Quantity                    | Deduction |
|----------------|-------------|-------|--------|-------|-------------------------------|-------|-----------------------------|-----------|
| i              | wall        | 2.000 | 55.500 | 0.225 | 0.250                         | 0.000 | 6.244                       | -         |
| ii             | road        | 1.000 | 55.500 | 3.050 | 0.200                         | 0.000 | 33.855                      | -         |
| Total Quantity |             |       |        |       | 40.09875 Sqm (Sqm)            |       | 40.09875 Sqm (Square Meter) |           |
| Amount         |             |       |        |       | 40.09875 X<br>216.23489289764 |       | 8670.75                     |           |

**Total Amount (A) : 293369.08**

**Additional Components**

| # | Item Name                           | Remark | Amount (in Rs.) |
|---|-------------------------------------|--------|-----------------|
| 1 | Provision for Contingency @ Rs.3000 | -      | 3000            |
| 2 | Display Citizen Board @ Rs.3629.92  | -      | 3629.92         |

**Additional Components Amount (F) : 6629.92**

**Grand Total Amount (A + F) : 299999.00068815**

**MANA DEOGAM  
JE  
Dharmasala Block**

**RAJAT KUMAR MOHAPATRA  
AEE  
Dharmasala Block**

**Jyotirmaya Kar  
BDO  
Dharmasala Block**