

## Detailed Estimate

**OD/364/3484/120004/430337/00102979 : Const of CC road at Damru sahi padampur village**

**Block : Malkangiri, Gram Panchayat : Sindrimal**

**Created By:Er Ch Roshan Patro**

<b>1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cutoff Wall	2.000	66.000	0.230	0.200	0.000	6.072	-
ii	Cross Cutoff Wall	2.000	3.290	0.230	0.200	0.000	0.303	-
<b>Total Quantity</b>						<b>6.37468 cum (cum)</b>	<b>6.37468 Cum (Cubic Meter)</b>	
<b>Amount</b>						<b>6.37468 X 240.77592</b>	<b>1534.87</b>	
<b>2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b>								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cutoff bed	2.000	66.000	0.230	0.050	0.000	1.518	-
ii	Cross Cutoff Wall	2.000	3.290	0.230	0.050	0.000	0.076	-
iii	Bed filling	1.000	65.540	3.290	0.100	0.000	21.563	-
<b>Total Quantity</b>						<b>23.15633 cum (cum)</b>	<b>23.15633 Cum (Cubic Meter)</b>	
<b>Amount</b>						<b>23.15633 X 567.017232</b>	<b>13130.04</b>	
<b>3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b>								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction

i	Cutoff Wall	2.000	66.000	0.230	0.350	0.000	10.626	-
ii	Cross Cutoff Wall	2.000	3.290	0.230	0.350	0.000	0.530	-
iii	C.C bed	1.000	65.540	3.290	0.100	0.000	21.563	-
Total Quantity					32.71835 cum (cum)		32.71835 Cum (Cubic Meter)	
Amount					32.71835 X 5563.1345602		182016.58	

**4. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc**

Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cutoff Wall	4.000	66.000	0.000	0.200	0.000	52.800	-
ii		2.000	66.000	0.000	0.100	0.000	13.200	-
Total Quantity					66 Sqm (Sqm)		66 Sqm (Square Meter)	
Amount					66 X 216.23489289764		14271.50	

**5. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	C.C bed	1.000	66.000	3.750	0.100	0.000	24.750	-
Total Quantity					24.75 cum (cum)		24.75 Cum (Cubic Meter)	
Amount					24.75 X 7048.4610834		174449.41	

**6. Earth Work (AR0114c) : Filling of foundation with excavated earth**

Filling in foundation and plinth with excavated materials in all kinds of soil including watering and ramming as directed by the Engineer-in-charge.

SI No	Description	No	L	B	D	CF	Quantity	Deduction
-------	-------------	----	---	---	---	----	----------	-----------

i		2.000	66.000	0.600	0.300	0.000	23.760	-
Total Quantity					23.76 cum (cum)		23.76 Cum (Cubic Meter)	
Amount					23.76 X 147.30633456		3500.00	

<b>Total Amount (A) : 388902.40</b>
-------------------------------------

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ 1%	-	3889.0240447384
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.2208	Hire charges of plate vibrator etc.	2208
<b>Additional Components Amount (F) : 11097.024044738</b>			

<b>Grand Total Amount (A + F) : 399999.42851858</b>
---

Er Ch Roshan Patro  
JE  
Malkangiri Block

Er. ABHIJIT SETHI  
AEE  
Malkangiri Block

Tapan kumar senapati  
BDO  
Malkangiri Block