

Detailed Estimate

**OD/345/3295/115986/421139/00102906 : CONST OF CC ROAD AT DUNGURIPALI BASTI TO UPARPADA Length 82
Mtr**

Block : Saintala, Gram Panchayat : Budabahal

Created By: Rajen Toppo

1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	cut off	2.000	165.000	1.000	1.000	0.000	330.000	-
Total Quantity						330 Cft (Cubic Foot)	9.344544 Cum (Cubic Meter)	
Amount						9.344544 X 240.77592	2249.94	
2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	cut off	2.000	165.000	1.000	0.500	0.000	165.000	-
ii	inner filling	1.000	165.000	10.500	0.500	0.000	866.250	-
Total Quantity						1031.25 Cft (Cubic Foot)	29.2017 Cum (Cubic Meter)	
Amount						29.2017 X 453.796232	13251.62	
3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	cut off	2.000	165.000	1.000	0.700	0.000	231.000	-
ii	inner	1.000	165.000	12.000	0.400	0.000	792.000	-

Total Quantity	1023 Cft (Cubic Foot)	28.9680864 Cum (Cubic Meter)
Amount	28.9680864 X 5012.97771876	145216.37

4. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	wall	2.000	165.000	0.000	0.700	0.000	231.000	-
Total Quantity					231 Sft (Square Foot)		21.460593 Sqm (Square Meter)	
Amount					21.460593 X 216.23489289764		4640.53	

5. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	CHIPS	1.000	165.000	12.000	0.349	0.000	691.020	-
Total Quantity					691.02 Cft (Cubic Foot)		19.567475136 Cum (Cubic Meter)	
Amount					19.567475136 X 6479.52977212		126788.04	

Total Amount (A) : 292146.50

Additional Components

#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ 1%	-	2921.4650102269
2	Display Citizen Board @ Rs.3000	-	3000
3	Any Other Lumpsum @ Rs.1932	micallaneous item	1932

Additional Components Amount (F) : 7853.4650102269

Grand Total Amount (A + F) : 299999.96603292

**JE
Saintala Block**

**Santosh Behera
AEE
Saintala Block**

**PURUSOTTAM MIRDHA
BDO
Saintala Block**