

## Detailed Estimate

**OD/350/3342/117093/399792/00062966 : Improvement Of Cc Road With Guard Wall From Yudhistir Guru House To Dolagobinda Guru House(Part-I), Vill. Sankilo**  
**Block : Nischinta Koili, Gram Panchayat : Kantarpada**  
**Created By:Pradeep Kumar Senapati**

<b>1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	G.WALL	2.000	15.000	0.600	0.600	1.000	10.800	-
<b>Total Quantity</b>						<b>10.8 cum (cum)</b>	<b>10.8 Cum (Cubic Meter)</b>	
<b>Amount</b>						<b>10.8 X 240.77592</b>	<b>2600.38</b>	
<b>2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b>								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	G.WALL	2.000	15.000	0.600	0.600	1.000	10.800	-
<b>Total Quantity</b>						<b>10.8 cum (cum)</b>	<b>10.8 Cum (Cubic Meter)</b>	
<b>Amount</b>						<b>10.8 X 1086.157232</b>	<b>11730.50</b>	
<b>3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b>								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	G.WALL	2.000	15.000	0.600	0.600	0.150	1.620	-
ii	G.WALL	2.000	15.000	0.375	0.900	1.000	10.125	-
iii	ON ROAD	1.000	6.000	3.500	0.100	1.000	2.100	-
<b>Total Quantity</b>						<b>13.845 cum (cum)</b>	<b>13.845 Cum (Cubic Meter)</b>	

<b>Amount</b>	<b>13.845 X 6090.15944436</b>	<b>84318.26</b>
---------------	-----------------------------------	-----------------

**4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	WEARING COAT	1.000	15.000	3.500	0.075	1.000	3.938	-
Total Quantity						3.9375 cum (cum)		3.9375 Cum (Cubic Meter)
<b>Amount</b>						<b>3.9375 X 7559.06192932</b>		<b>29763.81</b>

**5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc**

Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	G.WALL	4.000	15.000	0.900	1.000	1.000	54.000	-
ii	ROAD SIDES	2.000	15.000	0.100	1.000	1.000	3.000	-
Total Quantity						57 Sqm (Sqm)		57 Sqm (Square Meter)
<b>Amount</b>						<b>57 X 216.39264180804</b>		<b>12334.38</b>

**Total Amount (A) : 140747.32**

**Additional Components**

#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ Rs.1438	-	1438
2	Display Citizen Board @ Rs.1617.5	-	1617.5
3	Provision for survey investigation and quality control @ Rs.0	-	0

**Additional Components Amount (F) : 3055.5**

Grand Total Amount (A + F) : 143802.82247852

**Pradeep Kumar Senapati**  
**JE**  
**Nischinta Koili Block**

**Nalinikanta Mohapatra**  
**AEE**  
**Nischinta Koili Block**

**Dibyendu Kumar Das**  
**BDO**  
**Nischinta Koili Block**